

Kelly Down Drilling Co., Inc.

Ind

K. W. Laymon
Drilling Contractor
&
Oil Producer

④

Route 1

Neosho Falls, Kansas 66758

Phone: (316) 963-2495

April 9, 1986

Laymon Oil Company
Rt. 1 Box 84
Neosho Falls, Kansas 66758

28-8-20E
NE 5.1J

Lloyd Noll No. 1-86
Spudding Date: 4/7/86
Completion Date: 4/9/86
Bit Size: 6 1/4"

Soil & Clay	0 - 41
Lime	41 - 56
Shale	56 - 124
Lime & Shale	124 - 578
Black Shale	578 - 584
Lime & Shale	584 - 886
Big Shale	886 - 923
Lime	923 - 967
Shale	967 - 1020
Lime	1020 - 1026
Shale w/lime str.	1026 - 1094
Shale	1094 - 1213
Lime	1213 - 1226
Shale	1226 - 1334
Lime	1334 - 1341
Shale	1341 - 1626
Mississippi Lime	1626 - 1640
Total Depth	1640

APR 21 1986

WICHITA SURVEY
WICHITA, KANSAS

Set 49.90' of 7" surface.
Plugged well with 15 sacks
of cement on bottom, 15 sacks
@ 886', cemented 350' to
surface. Cemented by Consoli-
dated, 4/9/86 10:00 A.M.

RECEIVED
STATE CORPORATION COMMISSION

APR 17 1986

CONSERVATION DIVISION
Wichita, Kansas