

32-8-20E

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS


COMPANY ROSEN OIL

SEC. 32 T. 8 R. 20E
LOC. NW NE SW

FARM Strange NO. 1

COUNTY Jefferson

TOTAL DEPTH 1487'
COMM. 7-12-68 COMP. 9-5-68
SHOT OR TREATED
CONTRACTOR D. D. Sandlin
ISSUED 10-19-68



CASING

20	10	
15	XR 7" '65'	cem w/ 50 sx
12	6	
13	5	
	4 1/2" ;482'	cem w/ 50 sx

FIGURES INDICATE BOTTOM OF FORMATIONS

ELEVATION 1056' KB
PRODUCTION 3,650,000 CFGPD/
McLouth 1484

2	soil	2
15	clay	15
11	sandstone	28
16	shale	44
23	lime w/ shale st	67
56	shale	123
14	sandy shale	137
29	lime	166
5	shale black	171
5	lime	176
11	shale	187
10	lime	197
22	shale	219
32	lime w/ shale st	251
197	shale	418
37	lime	485
10	shale	495
20	lime	515
19	shale	534
16	lime w/ shells	550
16	sandy lime	566
24	shale	590
190	lime w/ shells	780
125	shale	905
85	shale w/ lime st	990
450	sandy shale	1410
27	shale w/ lime st	1467
8	gas sand	1475
2	shale	1477
6	sand(some oil show)	1483
4	sandy shale	1487

TOPS: SMP	450
Lansing	592
Kansas City	778
Base Kansas City	915
Marmaton	1010
Cherokee	1466
McLouth	4187
RTD	

T.D.

Set 65' of 7" surface pipe an cemented to surface
Cored from 1467' to 1487'
Set 1479' of 4" pipe , cemented with 50 sacks.