

AUG 1 1970

D. D. Sandlin Drilling Co.

Rotary Drilling -- Diamond Coring

DRILLED FOR: ROSEN OIL CORPORATION
6 MILLER # 2

SEC 32 -8south 20 east
JEFFERSON COUNTY, KANSAS
APRIL 1970

32-8-20E

C SW NE

Elv. 1037' DF

THICKNESS	FORMATIONS	TOTAL DEPTH
20	soil on clay	20
5	lime	25
3	shale	28
26	lime w/ shale st	54
19	shale w/ lime st	73
17	shale	90
10	sand hard	100
13	shale	113
32	lime (rough)	145
3	shale black	148
5	lime	153
12	shale w/ shells	165
9	lime	174
128	shale w/ lime shells	302
120	shale	422
68	lime	490
20	shale	510
15	lime	525
42	shale	567
98	lime	665
85	lime w/ shale st	750
143	shale	893
14	lime	907
29	shale	936
50	shale w/ lime st	986
149	sandy shale	1135
20	lime	1155
3	shale black	1158
182	shale w/ lime st	1240
10	lime	1250
146	shale	1396
5	lime	1401
77	shale	1478
6	lime(miss)	1484

Dry/miss

LKC 430
KC 565
BKC 750
miss ls. 1478



T.D.

Set 62' of 7" surface pipe and cemented to surface.
Cored from 1431' to 1471'
Set 1480' of 4" pipe and cemented with 50 sacks.