


IMPORTANT
Kans. Geo. Survey request
samples on this well.

S. 19 T. 8 R. 21 E

Loc. N2 NE

County Leavenworth



Elev.: Gr. 896

DF _____ KB 900

API No. 15 — 103 — 20,022
County Number

Operator Tomlinson Oil Company		
Address 200 West Douglas, Suite 1030 Wichita, Kansas 67202		
Well No. #1	Lease Name Edmonds	
Footage Location 660 feet from (N) (S) line 1320 feet from (E) (W) line		
Principal Contractor B & N Drilling Co.	Geologist Bill Iverson	
Spud Date 5-28-75	Total Depth 1380	P.B.T.D. 1322
Date Completed 6-3-75	Oil Purchaser	

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	9"	7"			Posmix	75	
Production	6 1/4"	4 1/2"		1376	Posmix	60	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	DP	1267-79'

Size	Setting depth	Pecker set at
2 3/8"	1370	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
10,000 GCKCl WTR + 5000# 20-40 sand	1267-79
150 G 15% NE Acid	1267-79

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Tomlinson Oil Co., Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Edmonds	Temp Abnd
S 19 T 8 R 21 E W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil & Clay	0	33	BKC	551
Shale/Sand	33	45	cher	790
River Gravel	45	62	Miss	1290
Shale	62	226		
Lime	226	230		
Shale	230	234		
Lime	234	248		
Shale	248	252		
Lime	252	255		
Shale	255	275		
Sand	275	289		
Sand/Shale	289	307		
Lime	307	316		
Shale	316	372		
Lime	372	386		
Sandy Shale	386	391		
Lime	391	397		
Shale	397	409		
Lime	409	419		
Sandy Shale	419	449		
Lime	449	459		
Sandy Shale	459	469		
Lime	469	471		
Sandy Shale	471	480		
Lime	480	503		
Sandy Shale	503	513		
Lime	513	555		
Sandy Shale	555	694		
Lime	694	699		
Sandy Shale	699	743		
Lime/Shale	743	805		
Sandy Shale	805	1060		
Lime	1060	1082		
Shale	1082	1234		

CONTINUED ON PAGE -2-

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

RECEIVED STATE GEOLOGICAL SURVEY OF KANSAS 1975 11/23/75	Date Received 11/23/75	Signature <i>Raymond E. Palmer</i>
		Title Geologist
		Date September 25, 1975

Tomlinson Oil

19 8-21E

1 Edmonds

WELL LOG (Cont.)

<u>Formation Description</u>	<u>Top</u>	<u>Bottom</u>
Lime & Shale	1234	1290
Lime	1290	1380

DST #1, 1055-1234', 15-30-30-30, strong blow, Rec. 1006' SWCM. IFP, 18-132#. FFP, 148-227#. IBHP, 375#. FBHP, 365#.

DST #2, 1267-1293', 30-30-90-90, weak to fair blow. Rec. 8' SGC HVY oil, 32' WCM. IFP, 25#. FFP, 35#. IBHP, 79#. FBHP, 168#.

DST #3, 1293-1380, 30-30-120-90, strong blow. Rec. 357' WCM, slightly oil specked, 250' SW, 620 SG & OCM. IFP, 10-116#. FFP, 126-310#. IBHP, 448#. FBHP, 442#.