

KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCH

S. 19 T. 8 R. 21E E
W

API No. 15 — 103 — 20020
County Number

Loc. SE SW

County Leavenworth

Operator

Tomlinson Oil Co., Inc.

Address

200 W. Douglas, Suite 1030, Wichita, Kansas 67202

Well No.

#2

Lease Name

Jones

Footage Location

660 feet from (N) (S) line 1980 feet from (E) (W) line

Principal Contractor

B & N Drilling Co.

Geologist

Bill Iverson

Spud Date

5-23-75 ✓

Total Depth

1344


P.B.T.D.

1340

Date Completed

5-28-75

Oil Purchaser



Locate well correctly

Elev.: Gr. 896

DF _____ KB 900

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	9"	7"		125	Common	75	3% CaCl
Production	6 1/4"	4 1/2"		1340	Posmix	100	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	D.P.	1275-81'
			4	D.P.	1274-80'

TUBING RECORD

Size	Setting depth	Packer set at
2"	1269	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
12,500 gal. gelled KCl wtr, 6500# 20-40 sand	1274-81
Sqz 75 sx Class "A" with 6% Halad-9	1274-81
Sqz 93 sx Class "A"	1274-81

INITIAL PRODUCTION

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) _____

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbis.	MCF	bbis.	CFPB

Disposition of gas (vented, used on lease or sold) _____ Producing interval (s) _____

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Tomlinson Oil Co., Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.

2

Lease Name

Jones

Temp Abnd

S 19 T 8 R 21 E

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil	0	6	BKC	556
Sand/Shale	6	221	Cher	792
Lime	221	246	Miss	1301
Sand/Shale	246	250		
Lime	250	253		
Sand/Shale	253	273		
Sand	273	289		
Sand/Shale	289	310		
Lime	310	382		
Sand/Shale	382	388		
Lime	388	462		
Sandy Shale	462	478		
Lime	478	504		
Sand/Shale	507	516		
Lime	516	532		
Shale/Lime	532	543		
Lime	543	558		
Shale	558	692		
Shale/Lime	692	698		
Sandy Shale	698	701		
Lime	701	759		
Shale	759	776		
Sandy Shale	776	1302		
Miss. Lime	1302	1344		

DST #1, 1224-1304', 15-30-85-90, GTS 15 min., G 57,300 CFG
 STAB in 55 min., 72'M, SIP 489-489#, FP 25-41#.

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Raymond E. Palmer
 Signature

Geologist

Title

September 25, 1975

Date