

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock,
Wichita, Kansas

27-8-4E

Company- PURE OIL CO.
Farm-A.D. Mall

No. 1

SEC. 27 T. 8 R. 4E
SW SW SW
330' N SL 330' E WL SW

Total Depth. 1944'

Comm. 11-29-57

Comp. 12-8-57


Shot or Treated.

Contractor. Shira Drlg. Co.

Issued. 4-26-58

County Clay

KANSAS



Elevation. 1262' DF

Production. Dry

Figures indicate Bottom of Formations.

All Meas. fr top K.B. 1' above DF

soil	5
clay	25
red bed	36
shale	105
shale, lime	315
shale, shells	490
lime, shale	640
shale	755
lime, shale	895
shells, shale	1095
Brkn lime, shale	1126
lime	1140
lime, brkn, shale	1284
lime w/some shale	1324
lime w/some shale	1384
shale	1418
lime, brkn, shale	1434
lime, brkn, shale	1453
lime w/ooc. shale	
brks	1770
shale, w/interbedded	
lime	1908
chert, tripolitic	
w/trace shale	1916
Interbedded chert	1935
lime, xylvn to slightly	
chalky, cherty in part	1944

Total Depth

TOPS: Geol.

Topeka	1095
Oread	1284
Heebner	1324
Brown Limestone	1418
Lansing	1434
Kansas City Lime	1542
Mississippi chert	1908
Mississippi lime	1935

Ran Schlumberger Log.