


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- SOHIO PETROLEUM CO.
Farm- Isenberg No. 1

SEC. 14 T. 10 R. 15W
SW SW SW

Total Depth. 3516 P.B. 3065
Comm. 2-10-52 Comp. 3-1-52
Shot or Trapped.
Contractor. Stearns Drlg.
Issued. 5-17-52

County Osborne
KANSAS



CASING:
8 5/8" 318.96' cem. w/200 sx.
5 1/2" 3537.98' cem. w/150 sx.

Elevation. 1861
(859m)
Production. 40.91 bbls. /
.2% wtr.

Figures indicate Bottom of Formations.

surface clay	40
shale & sand	180
shale & shells	314
shale	515
sand & shale	725
redbed & shale	1014
Anhyd.	1050
red bed & shale	1365
shale	1400
silt & shale	1690
lime & shale	2770
lime	2810
lime & shale	3032
lime	3065
lime & shale	3122
lime	3376
lime & congl.	3405
congl.	3515
congl.	3516
Total Depth P.B.	3065

Tops:

Tarkio	2517
Topeka	2727
Heobner	2973
Toronto	2995
Lansing	3023
Congl.	3396
Arbuckle	3500