

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

15-141-00059

Company- D.R. LAUCK OIL CO. & WHITESTONE PETROLEUM SEC. 2 T. 10 R. 15W  
Farm- Finnesy No. #1 SE SE NE

Total Depth. 3770'

Comm. 9-18-63

Comp. 9-28-63


County Osborne

KANSAS

Shot or Treated.

Contractor. D.R. Lauck Oil Co. & Whitestone Petroleum

Issued. 12-21-63



CASING:

Elevation. 1905' DE

8 5/8" 207' cem w/150sx

Production. DRY

Figures Indicate Bottom of Formations.

|                       |          |
|-----------------------|----------|
| surface clay          | 40       |
| blue shale            | 207      |
| shale & shells        | 415      |
| shale                 | 445      |
| sand                  | 465      |
| shale & shells        | 550      |
| sand                  | 670      |
| hard sand & pyrite    | 675      |
| shale & shells        | 780      |
| shale & sand          | 830      |
| red bed & shale       | 910      |
| shale, red bed & sand | 1125     |
| Anhydrite             | 1155     |
| shale & shells        | 1810     |
| lime & shale          | 2070     |
| shale & lime          | 2200     |
| lime & shale          | 2240     |
| sand                  | 2252     |
| shale & shells        | 2265     |
| shale & lime          | 2660     |
| shale & shells        | 2670     |
| broken lime & shale   | 2815     |
| lime & shale          | 2920     |
| shale & lime          | 2982     |
| lime & shale          | 3061     |
| shale                 | 3065     |
| lime                  | 3165     |
| shale & Dolomite      | 3230     |
| lime                  | 3358     |
| lime & shale          | 3445     |
| shale, lime & sand    | 3530     |
| Conglomerate, mostly  |          |
| chert                 | 3595     |
| shale, lime & chert   | 3650     |
| shale & lime          | 3715     |
| Simpson               | 3745     |
| Arbuckle              | 3770 RTD |
| Total Depth           |          |

| TOPS: LOG           | SMP   |
|---------------------|-------|
| Anhydrite           | 1125  |
| Heebner             | 3061  |
| Toronto             | 3085  |
| Lansing-Kansas City | 3113  |
| Base Kansas City    | 3381  |
| Conglomerate        | 3496  |
| Conglomerate Sand   | 3500  |
| Viola               | 36332 |
| Simpson             | 3616  |
| Arbuckle            | 3740  |

DST #1 (W) 3068-3095, Op 30 min. Weak  
blow 5 min. Rec. 5' mud. ISIP 581# 30  
min; FSIP 70# 30 min; IFP 31#; FFP 31#.

DST #2 (W) 3134-3165, Op 30 min Weak  
blow 5 min. Rec. 5' mud. ISIP 1054# 30  
min; FSIP 150# 30 min; IFP 39#; FFP 43#.