

15-141-20079
2-10-15W

State Geological Survey
WICHITA, BRANCH

CONTRACTOR'S WELL LOG

OPERATOR:	Thornton E. Anderson
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	FINNISSEY #1
LOCATION:	C S/2 S/2 NE, Section 2-10S-15W Osborne County, Kansas
SPUD DATE:	10-01-80
COMPLETION DATE:	10-07-80

0	270	Sand & Shale
270	890	Shale & Sand
890	1094	Shale
1094	1126	Anhydrite
1126	1828	Shale
1828	2030	Lime & Shale
2030	2410	Shale
2410	2855	Lime & Shale
2855	3520	Lime
	3520	Rotary Total Depth

Spud hole @ 7:30 p.m. 10-01-80. Drilled 313' of a 12-1/4" hole. Ran 7 joints of 8-5/8" 24# casing (tally 303.62') Set @ 312'. Cemented with 200 sx. of common, 2% gel, 3% c.c. Cement did circulate. Plug was down @ 2:00 a.m. 10-02-80.

T.D. 3520'. Set 1st plug @ 660' with 60 sx., 2nd plug @ 300' with 30 sx., 3rd plug @ 40' solid bridge with 10 sx. Rathole with 5 sx. 50/50 posmix, 4% gel. Plug was down @ 10:00 p.m. 10-07-80.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the FINNISSEY #1, C S/2 S/2 NE, Section 2-10S-15W, Osborne County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 15th day of October, 1980.