

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-141-00057

Company- D. R. LAUCK OIL CO., INC.
Farm- Meyer No. 1

SEC. 11 T. 10 R. 15W
NE NE NE

Total Depth. 3775
Comm. 6-20-57 Comp. 7-2-57
Shot or Treated.
Contractor.
Issued. 8-3-57

County Osborne
KANSAS



CASING:
8 5/8 213' w/ 165 sx cmt.

Elevation. 1856 DF

Production. Dry

Figures indicate Bottom of Formations.

shale & shells	540
sand	560
shale	690
sand	780
shale & red bed	1097
anhydrite	1120
shale, shells & red bed	1430
shale & shells	1650
lime & shale	1900
lime	1935
lime & shale	2840
lime	3035
lime & shale	3100
lime	3425
lime & shale	3505
shale	3571
chert, lime & shale	3665
lime & shale	3722
Arbuckle	3775
Total Depth	

TOPS:	SAMPLE	HALLIBTN.
Anhydrite	1097	
Heebner	3031	3028
Toronto	3053	3051
Lansing	3081	3078
Base KC	3350	3349
Conglomerate	3467	3462
Viola	3612	3609
Simpson	3696	3697
Arbuckle	3722	3722

DST #1: 3037-67, open 1 hr. wk. bl.
6 min. rec. 5' mud, BHP 240#/20 min.