

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas

15-41-00252


Company- ANDERSON-PRICHARD OIL CORP.  
Farm- Schbh No. 1

SEC. 15 T. 10 R. 15W  
SE SE SE

Total Depth. 3470  
Comm. 4-27-52 Comp. 5-8-52

County Osborne  
KANSAS

Shot or Treated.  
Contractor. Glenn W. Peel  
Issued. 6-28-52



Elevation. 1888 R.B.  
1885 (m)  
Production. 93 BO & 10 wtr.

CASING:

8 5/8" 195' cem.  
5 1/2" 3469' cem.

Figures Indicate Bottom of Formations.

surface clay & shale	199
shale	305
shale & sand	775
sand	810
shale	1035
anhyd.	1075
shale	1655
lime	2125
lime & shale	2860
lime	3400
lime & congl.	3425
lime	3470 RTD
Total Depth	

Tops:	
Anhyd.	1042
Heebner	2996
Toronto	3017
Lansing	3046
Congl.	3408
Simpson	3467

D.S.T. 3050-85, op. 1 hr., fair blow,  
rec. 90' very slightly oil cut mud.  
BHP 870#.

D.S.T. 2 3100-40, op. 1 hr., strong  
blow throughout rec. 120' gassy very  
slightly oil cut mud, and 30' oil  
and muddy oil, 780' gassy muddy oil,  
total fillup 930' BHP 1100#, FP 280#.

D.S.T. # 3: 3241-49 op. 1 hr., weak blow, rec.  
30' watery mud slightly oil cut, BHP 0.

D.S.T. # 4: 3399-3425, op. 1 hr., weak  
blow rec. 115' oil cut mud, BHP 770#.

P. 118 to 1/18% wtr/20 hrs. 13-38" SPM

P 58 BO 1/14 1/2 BW/16 hrs. 13-24" SPM

P 63 BO & 16 BW/18 hrs. 12-34" SPM

P. 74 BO & 14 BW/16hrs. 13-38" SPM

P 73 BO & 14 BW/24 hrs. 13-38" SPM

1 1/2" 3469'

MI & rigged up CT, swb. mud drld. cem.  
& CO to 3435. Perf. 3406-12 w/4 shaped  
charges per ft., 1 hr. bail test-17 GOPH  
w/tr. wtr.,; perf. 3420-26' w/4 shaped  
charges per ft. re-perf. 3420-26 w/4 shaped  
charges per ft. re-perf. 3420-26 w/4 shaped  
charges per ft. re-pref. 3414-20 w/2 1/2  
shaped charges per ft., 7 hrs. bail.  
re-perf.

35 GOPH w/ tr. wtr. Ran tubing & treated  
w/packer retrievable packer set @ 3360 Treated  
perfs. 3406-12 & 3414-26 w/1500 gals.  
Gel-X-500, Gel-X-500 broke down w/oil  
max press. 2400# min. press. 1000#  
pulled tubing & rods, swab 110B load  
oil & Gel, swb. 26 B load, 20 hrs. 100 BO  
1/5% wtr. Swb. rate of 4 1/2 BOPH for last  
12 hrs. RT&R.