

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

500 East Murdock,

Wichita, Kansas

15-141-00253


Company- AMERADA PETROLEUM CORP.

Farm- Esther Koelling No. 2

SEC. 22 T. 10 R. 15W
NE SE NE

Total Depth. 3391
Comm. 3-2-52 Comp. 3-17-52
Shot or Treated.
Contractor. Peol Brother, Inc.
Issued. 5-10-52

County Osborne
KANSAS



Elevation. 1835 D.F.

CASING:

8 5/8" 200' cem.
5 1/2" 3390' cem.

Production. I.P. 386 bbls. /
25% wtr.

Figures indicate Bottom of Formations.

sand & sod	40
shale & shells	200
shale	550
sand & pyrite	635
shale & shells	750
red bed & shale	985
anhyd.	1015
shale & shells	1820
shale & lime	2335
shale & shells	2550
lime brkn	2595
shale & lime	2770
lime	2892
lime & shale	2965
lime	3310
lime & congl. sand	3368
congl.	3391
Total Depth	

Sch. tops:

Heebner	2945
Lansing	2997
Congl.	3373

D.S.T. 2998-3050, open 2 hrs., Rec. 160'
of rotary mud, sl. oil & gas cut, 1040'
muddy oil; 1042 BHP

D.S.T. 3050-3092, open 2 hrs. Rec. 510' muddy
oil; 250' salt wtr; D.S.T. 3356-3391, open
2 hrs. Rec. 870' muddy wtr. w/trace oil;
715' sl. muddy oil; 355' salt wtr, 890' BHP