

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas


15-141-00254

Company- ANDERSON-PRICHARD OIL CORP.  
Farm- Ruggles "A" No. 6

SEC. 23 T. 10 R. 15W  
SE SE NW

Total Depth. 3437  
Comm. 6-5-52 Comp. 6-16-52  
Shot or Treated.  
Contractor. Glenn W. Peel  
Issued. 8-9-52

County Osborne  
KANSAS



CASING:  
8 5/8" 252' cem.  
5 1/2" 3850' cem.

Elevation. 1852 R.B.  
1849 (M)  
Production. State Phys. Prod.  
test 51 bbls. 1 1/2 wtr.

Figures Indicate Bottom of Formations.

surface soil	252
shale & sand	450
red bed	500
shale	775
shale & sand	990
anhyd.	1020
shale	1550
lime & shale	1960
lime	2210
lime & shale	2500
lime	2630
lime & shale	2755
lime	3437
Total Depth	

SPM. P. 45 BO & 1 1/2 BW in 24 hrs. 12-28"  
SPM. 24 hrs. state phys. prod. test:  
51 BO & 1 1/2 BW 14028" SPM. 1 1/2" pmp.

Tops:	
Hebner	2965
Toronto	2986
Lansing	3013
Congl.	3374
Simpson	3429

D.S.T. # 1; 2972-3005, op. 1 hr.  
shut in 15 min., good blow thruout  
Rec. 140' gassy CM BHP 100#. slowly  
incr.  
D.S.T. # 2; 3034-50, op. 1 hr. 10 min.  
shut in 20 min. good blow thruout  
test rec. 90' MCO BHP 820#.  
D.S.T. # 3; 3056-82, op. 1 hr. weak  
blow thruout test rec. 75' oil &  
GCWM and 100' MW BHP 950#.  
D.S.T. # 4 3170-3215, op. 1 hr. weak  
blow thruout test rec. 215' MSW  
BHP 540#.  
D.S.T. # 5: 3366-90, op. 1 hr. slight  
blow for 5 mins. rec. 5' mud, B HP 0.

Set 5 1/2" @ 3350' CO to 3300, perf.  
3042-44' w/4 shaped charges per ft.  
perf. 3044-50' w/6 shaped charges  
per ft. 15 hr. bailing test; 5 GO  
& 5 GEPH, oil incr. Az. w/500 gals.  
max. press. 450#. Pulled tubing.  
Dmp. 1 sx. cem. on top of junk @ 3300.  
Set Baker Model K CI Bridging plug @  
3010 w/2/3 sx. calseal. PBD 3008.  
Perf. w/4 shaped charges per ft.  
2986-89'. 24 hrs. swab test; 6 BO  
& 36 BW. Bailed 2 GOPH w/tr. wtr. for  
2 hrs. Az. w/500 gal. Gel-X-Etching  
acid max press. 600# min. press. 450#  
Total load 84 bbls. 4 hr. swab test:  
1 1/2 BFPH, 5% wtr. Swbd. 1 1/2 BFPH, 5%  
wtr in 19 hrs. R T&R 2 3/8" @ 2994.46  
P 50 1/2 BO & 1 1/2 BW in 24 hrs. 12-28"  
SPM. P 45 BO & 1 1/2 BW in 24 hrs. 12-28"  
SPM. P 50 BO & 1 1/2 BW in 24 hrs. 12-28"  
SPM. P. 50 BO & 1 1/2 BW in 24 hrs. 12-28"  
SPM P. 50 BO & 1 1/2 BW in 24 hrs. 12-28"  
SPM. P 50 BO & 1 1/2 BW in 24 hrs. 12-28"