

33-10-15th End p1

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

SIDE ONE

Compt. _____

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

F Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 51-22 EXPIRATION DATE _____

OPERATOR Woodman & Iannitti Drilling Company API NO. 15-141-20,145

ADDRESS 1008 Douglas Building COUNTY Osborne

Wichita, Kansas 67202 FIELD WC (Worley Abd)

** CONTACT PERSON K.T. Woodman PROD. FORMATION _____

PHONE 265-7650

PURCHASER N/A LEASE Angel

ADDRESS _____ WELL NO. 1

WELL LOCATION NW SE SE

DRILLING CONTRACTOR Woodman & Iannitti Drilling Company 990 Ft. from East Line and

ADDRESS 1008 Douglas Building 990 Ft. from South Line of

Wichita, Kansas 67202 the SE (Qtr.) SEC 33 TWP 10 RGE 15 (W).

PLUGGING CONTRACTOR Sun Oil Well Cementing

ADDRESS P.O. Box 169

Great Bend, Kansas 67530

TOTAL DEPTH 2891' PBTD _____

SPUD DATE 9-24-82 DATE COMPLETED 9-28-82

ELEV: GR 1927 DF 1929 KB 1932

DRILLED WITH (~~OPEN~~) (ROTARY) (~~OPEN~~) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE _____

Amount of surface pipe set and cemented 245' DV Tool Used? _____

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, (Dry) Disposal, Injection, Temporarily Abandoned, OWWO. Other _____

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

K.T. Woodman, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

K.T. Woodman
(Name)

State Geological Survey
WICHITA BRANCH

WELL PLAT

			+

(Office Use Only)
KCC _____
KGS
SWD/REP _____
PLG. _____

70865

SIDE TWO

ACO-1 WELL HISTORY

OPERATOR **Woodman & Iarnitti Drlg.** LEASE **Angel**

SEC. **33** TWP. **10** RGE. **15W**

FILL IN WELL INFORMATION AS REQUIRED:

WELL NO. **1**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<input checked="" type="checkbox"/> Check if no Drill Stem Tests Run.				
Clay & Post Rock	0	40	Anhydrite	1057 (+875)
Shale	40	254	Topeka	2800 (-868)
Shale	254	591		
Pyrite & Hard Sand	591	598		
Pyrite & Hard Sand	598	610		
Shale & Sand Streaks	610	1057		
Anhydrite	1057	1090		
Shale & Lime	1090	1550		
Lime & Shale	1550	1830		
Lime & Shale	1830	2080		
Lime & Shale	2080	2330		
Shale & Lime	2330	2515		
Lime & Shale	2515	2705		
Lime & Shale	2705	2845		
Lime & Shale	2845	2891		
R.T.D.	2891			
**No Logs				

If additional space is needed use Page 2, Side 2

Report of all strings set — surface, intermediate, production, etc. **CASING RECORD** (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"		245'	Common	160	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD					
Size	Setting depth	Packer set at			

DRILLERS LOG

15-141-20040
33-10-15W

No. 1 Ross

CASING RECORD: 8 5/8" @ 245.73'
w/160 sx cement

COMPANY: W-W Oil Company

CONTRACTOR: Red Tiger Drilling Company

COMMENCED: September 15, 1978

COMPLETED: September 26, 1978

DESCRIPTION: SE/4 SE/4 SW/4
Sec. 33-T10S-R15W
Osborne County, Kansas

ELEVATION: 2,032' KB

TOTAL DEPTH: 3,750'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Rock	0	20	
Shale	20	500	
Sand	500	570	
Sand & Shale	570	780	
Shale & Sand Streaks	780	890	
Red Bed	890	1217	
Anhydrite	1217	1256	
Shale	1256	1815	
Shale & Lime	1815	2167	
Lime & Shale	2167	2525	
Lime	2525	3750	
RTD		3750	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 2nd day of October, 1978.

James A. Hageman
Notary Public