

Plotted


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

CITIES SERVICE OIL CO.
Conger No. 1

SEC. 22 T. 10 R. 16 W
NEc NW
330' S 330' W of N $\frac{1}{4}$ cor.

Total Depth. 3689
Comm. 2-7-42 Comp. 2-26-42
Shot or Treated. None.
Contractor. Holm Drilling Co.
Issued. 4-11-42

County Rocks.



CASING.

85/8" 2450

Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

rock and sand 25
shale and shells 65
shale blue 162
shale and shells 245
shale blue soft 254
shale and shells 535
shale red 637
shale red and shells 750
shale blue & lime shells 870
sand light soft 885
shale and shells 1145
shale red and shells 1240
anhydrite 1280
shale and shells 1415
shale red and shells 1540
shale shells & salt 1790
shale and shells 1820
lime light hard 1880
lime light broken 1923
lime grey hard 1991
lime light shale break 2030
shale and lime shells 2090
lime & shale breaks 2108
lime light hard 2294
lime broken 2311
lime grey hard 2381
lime broken med 2397
lime light med 2413
lime broken med 2475
shale and shells 2525
lime grey hard 2617
lime broken 2652
lime grey hard 2710
shale and shells 2751
shale & lime shells 2840
lime and shale broken 2916
lime grey hard 2965

lime grey hard 3232
lime light hard 3277
lime cored (Rec 2') 3282
lime light hard 3540
lime and shale 3561
chert and shale 3578
conglomerate 3600
conglomerate and chert 3612
conglomerate 3630
lime rough hard 3635
lime light hard 3647
dolomite 3689

Total Depth.

TOP Lansing 3208
cherty conglomerate 3557
Erosional Arbuckle 3623
Top Arbuckle 3639
Penetration 50'

3640-89 Fair to Good porposity,
no saturation.

OWWO See Comp. card.
(oil well)