

2-10-16W

15-103-21342

OPERATOR: McGinness Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: BECKER #1
 LOCATION: NW SE NW, Section 2-10S-16W
 Rooks County, Kansas
 SPUD DATE: 6/18/81
 COMPLETION DATE: 6/25/81

0	283	Clay & Shale
288	1146	Shale
1146	1177	Anhydrite
1177	2609	Shale
2609	2802	Shale & Lime
2802	2904	Lime & Shale
2904	3021	Shale & Lime
3021	3215	Lime & Shale
3215	3240	Shale & Lime
3240	3358	Lime & Shale
3358	3380	Shale & Lime
	3380	Rotary Total Depth

Spud hole @ 5:30 p.m., 6/18/81. Drilled 288' of a 12 1/4" hole. Ran 7 joints of 8 5/8" casing set @ 285' K.B. Cemented with 180 sacks of common 2% gel, 3% c.c. Cement did circulate. Plug was down @ 6:00 a.m., 6/19/81.

TD 3380'. Ran 82 joints of 4 1/2" 9 1/2# casing set @ 3372'. Cemented with 175 sx. of common 2% Gel, 3% gel. Ran 10 barrels Salt Flush. Pumped plug to 3358'. Job complete 6/25/81.

SAMPLE TOPS:

Anhydrite 1146' - 1177'

STATE OF KANSAS

COUNTY OF SEDGWICK

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the BECKER #1, NW SE NW, Section 2-10S-16W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Vice Pres.

RECEIVED
 STATE CORPORATION COMMISSION
 JUL - 1 1981
 CONSERVATION DIVISION
 Wichita, Kansas