

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-163-71782

Company- CITIES SERVICE OIL COMPANY
Farm- Erway No. 5

SEC. 2 T. 10 R. 16W
SW SW SE
330' N. & 330' E. of S/4 cor.

Total Depth. 3856 SLM

Comm. 7-3-53

Comp. 9-21-53


Shot or Treated.

Contractor. Lohmann-Johnson Drlg. Co., Inc.

Issued. 11-7-53

County Rooks

KANSAS



CASING:

8 5/8" 241' cem. w/175 sx

5 1/2" 3436' cem. w/200 sx

Elevation. 1932

Production. SWD

Figures indicate Bottom of Formations. Input Test: 210' bbls per hr. 10-13-53

shale & shells	242
shale	510
shale, shells & redbed	1030
red bed	1085
anhydrite	1121
shale & shells	1975
lime (Hole 6° off at	2075
2000' P.B. to 1300' with	
360 sx cement and redrilled	
1300-2075 to straighten hole.)	
lime & shale	2075-2135
shale	2255
shale & lime	3050
lime	3067
lime & shale	3085
lime	3390
lime & conglomerate	3442
3442 RTD = 3440 SIM	
lime & shale	3455
lime	3467
lime & shale	3480
lime	3500
sandy lime	3520
lime	3580
sandy lime	3600
lime	3660
sandy lime	3685
lime	3753
cherty lime	3789
sandy lime	3830
lime	3867
3867 sand lime = 3856 SIM	
Total Depth	

Tops: Corr.

Topeka	2799
Heebner	3026
Dodge	3046
Lansing	3071
Conglomerate	3401
Arbuckle	3432

Penetration 424'