


THE PALMER OIL CORP.
Baum No. 1.

SEC. 10 T. 10 R. 16 W.
CSL SW NE

Total Depth. 3520
Comm. 2-19-42 Comp. 3-6-42
Shot or treated.
Contractor. The Palmer Oil Corporation.
Issued. 4-18-42

County Rooks.



CASING.

10" 111'8
5 1/2" 3248' cemented.

Elevation.

Production. Pot. 210 B.

Figures Indicate Bottom of Formations.

shale and sand	85
shale and shells	205
shale and sand	655
anhydrite	660
shaly shells hard	665
sand	760
shale blue	780
sand	825
red bed and sand	975
red bed and iron	1105
iron	1110
anhydrite	1148
shale and salt	1295
shale and shells	1450
shale and salt	1605
shale	1935
lime	2054
broken lime	2522
shale and shells	2635
lime	2656
broken lime	2844
lime	2976
lime soft	2988
lime Odor in 3010 samples	3020
broken lime	3038
lime Odor in 3090 samples	3296
broken lime	3350
lime	3462
shale	3494
lime	3520
Total Depth.	

Perforated at 1100' cemented.