

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


15-163-03484

Company - CITIES SERVICE OIL CO.
Farm - Comp No. 1

SEC. 12 T. 10 R. 16W
NE 1/4 NE 1/4
330' S & 330' E of NE Corner

Total Depth. 3343'
Comm. 2-6-48 Comp. 5-28-48
Shot or Treated. Acid. 9,000 gallons (see below)
Contractor. R. L. Mine Drlg. Co.
Issued. 7-10-48

County. Rooks
KANSAS



8-5/8" 230' Cem. W/150 Sx.
4-1/2" 3343' Cem. W/150 Sx.

Elevation. 1933 ft.

Production. Pump 5 1/2 B0, 22 BW
in 8 hours.

Figures Indicate Bottom of Formations.

sand	40
shale & shells	230
shale & lime	815
shale, shells & sand	1030
shale & shells	1095
anhydrite	1150
shale & shells	1260
lime & shale	1980
lime	2400
lime & shale	2465
twisted off drill pipe; could not recover fish cem. 1663' to 1416' W/ 200 sx. cme. & 300% C.C.	
shale & lime	1416-1755
lime & shale	3010
lime	3120
lime & shale	3180
lime	3343
Total Depth	

Tops:
Lansing 3084
Penetration 259
total depth 3343
Perf. Pen. Lansing 251

Drilled cement to 3343'

Perforate 26 shots	3188-95	small show oil
" 36 "	3138-50	"
" 30 "	3119-27	"
" 30 "	3083-95	"
" 30 "	3061-69	"

3-16-48 acidized 1000 gals.	3061-69
" " 1000 "	3083-95
" " 1000 "	3119-27
" " 1000 "	3138-50
" " 1000 "	3188-95

3-20-48 Pumped 12 oil, 29 wtr 24 hrs.
3-22-48 Pumped 15 oil, 17 wtr 24 hrs.

perforate 16 shots 3331-35
Perforate 24 shots 3293-3304
Perforate 24 shots 3274-80
Perforate 24 shots 3228-34

3-28-48 Acidized 1000 galls	3331-35
" " 1000 "	3293-3304
" " 1000 "	3274-80
" " 1000 "	3228-34