

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


15-163-00765

Company- CITIES SERVICE OIL CO.  
Farm- Rogers No. 1

SEC. 14 T. 10 R.16W  
NW SW NW  
990' N & 330 E of W/4 Corner

Total Depth. 3520'  
Comm. 4-25-58 Comp. 5-8-58  
Shot or Treated.  
Contractor. Lohmann-Johnson Drlg.  
Issued. 6-28-58

County Rooks  
KANSAS



Elevation. 1909' Gr.

Production. Dry

Figures Indicate Bottom of Formations.

sand & shale	320
shale	1105
anhydrite	1134
shale & lime	1770
lime	2124
lime & shale	2260
lime	2518
shale	2653
lime & shale	2742
shale & lime	2820
lime	3271
lime & shale	3322
lime	3424
lime & conglomerate	3437
lime	3475
conglomerate & lime	3516
lime	3520
Total Depth	

TOPS:	
Anhydrite (scout)	1105
Topeka	2804
Heebner	3039
Dodge	3063
Lansing	3085
Base Kansas City	3361
Conglomerate	3428
Arbuckle	3490
Pen.	30'

DST 2826-50, op 1 hr, rec. 37' slightly  
oil-cut mud. BHP 850# in 30 mins.

DST 3045-76, op 1 hr, rec. 14' mud;  
BHP 85# in 45 mins.

DST 3090-3106, op 1 hr, rec. 9' mud with  
trace oil. BHP 33# in 45 mins.

DST 3109-30, op 1 hr, rec. 42' watery mud  
BHP 1120# in 45 mins.

DST 3243-71, op 1 hr, rec. 12' mud.  
BHP 350# in 45 mins.

DST 3416-37, op 1 hr, rec. 22' mud  
BHP 215# in 45 mins.