

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY ✓

508 East Murdock,

Wichita, Kansas


15-163-0835

Company- CITIES SERVICE PETROLEUM COMPANY
 Farm- Smith "U" No. 2

SEC. 15 T. 10 R. 16W
 SW NE SE
 1650' N & 990' W of Sec.

Total Depth. 3624' PB 3588'
 Comm. 3-26-62 Comp. 4-14-62
 Shot or Treated.
 Contractor. Peel Bros., Inc.
 Issued. 11-3-62

County Rooks
 KANSAS



CASING:
 8 5/8" 239' cem w/200 sx.
 5 1/2" 3600' cem w/200 sx.
 DV tool @ 1279' cem w/300 sx. & 200 cu. ft.
 Stratacrete.

Elevation. 2093' DF
 Production. Pot. 33 BO & 55 BWPD

Figures Indicate Bottom of Formations.

lime		60
shale & shells		239
shale, shells & sand		650
shale & sand		730
sand		760
sand & pyrite		840 ✓
sand		900
red bed & shale		1215
shale		1260
anhydrite		1290
shale & shells		1805
lime & shale		2325
shale & lime		2485
lime		2605
lime & shale		2810
shale & lime		2910
lime		3175
lime & sand		3235
lime		3575
conglomerate		3600
lime		3605 RTD
lime		3624
Total Depth		
PLUGGED BACK		3588'
TOPS: LOG		
Anhydrite	1255	1290
Topeka	2955	
Heebner	3186	
Toronto	3206	
Lansing	3232	
Base Kansas City	3504	
Basil Pennsylvania Sand	3560	
Cherty Conglomerate	3572	
Arbuckle	3600	