

15-103-01841

**KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY**  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY W. L. HARTMAN

SEC. 34 T. 10 R. 16W  
LOC. CE<sup>1</sup><sub>2</sub> SE SE

FARM O'Leary


NO. 1

TOTAL DEPTH 3575<sup>1</sup>/<sub>2</sub> PB 3520  
COMM. 8-15-50

COMP. 11-21-50

COUNTY Rooks

SHOT OR TREATED  
CONTRACTOR H & H Drlg Co.  
ISSUED 2-3-51



CASING

8 5/8" 166' cem w/125 sx  
5 1/2" 3560' cem w/200 sx

ELEVATION 2072 DF

Pot.  
PRODUCTION 36 bbls 13 hrs.

post rock	90
shale blue	166
shale	789
river rocks	793
shale	1223
anhydrite	1263
shale, shells	1775
shale	1860
lime, shale	1990
shale, shell, lime	2168
lime (Ft. Riley)	2278
lime	2300
shale, lime	2379
lime	2668
lime, shale	2925
lime	3072
lime, shale	3226
lime	3400
lime, shale	3467
lime	3477
lime, shale	3533
lime	RTD 3565
lime	3575 <sup>1</sup> / <sub>2</sub>

FIGURES INDICATE BOTTOM OF FORMATIONS

continious blow, rec. 32' muddy water w/spots of oil, good odor.  
BHP "0" 15 minutes.

DST #4 3325-3350, open 20 mintues, strong steady blow. Rec. 450' muddy water, spots of oil, no free oil, slightly gas cut. BGP 600# in 15 minutes.

DST #5 3352-3375, open 1/2 hour, weak steady blow, lo minutes, intermittant blow lo minutes, dead last 10 minutes. Rec. 20' mud, few oil spots. BHSIP 540#, 15 mins.

DST #6 3377-3400, open 1/2 hour, good steady blow throughout test. Rec. 90' heavily oil and gas cut mud. BHP 850# 15 minutes.

DST #7 3405-3436, open 1/2 hour, faint blow, lo minutes, intermittant blow, 20 minutes. Rec. 20' OCM. BHP "0", 15 minutes.

DST #8 3436-3467, open 1/2 hour, faint blow, 6 minutes, rec. 5' rotary mud, few spots of oil. 90# BHP, 15 minutes.

DST #9 3477-3506, open 1/2 hour, faint blow lo minutes, rec. 10' mud, slightly oil cut. BHP "0", 15 minutes.

DST #10 3560-3565, open 1 hour, fair steady blow throughtout test, rec. 63' heavily oil cut mud. BHP 780#, 15 mins.

Slope Test & SLM - OK @ 2270

Total Depth  
Plugged back to 3520

Tops:

Topeka	2957
Heebner	3194
Dodge	3216
Lansing	3238
Base-Kansas City	3504
Arbuckle	3558

DST #1 3218-3230, open 1 hour, weak intermittant blow, 15 mins., rec. 15' heavily oil cut mud. BHSIP "0", 1 hr. and 15 minutes.

DST #2 3260-3290, open 1/2 hr, weak blow for 15 minutes, rec. 20' slightly oil cut mud. 900# BHSIP, 15 minutes.

DST #3 3290-3324, open 1/2 hr., weak