

OCT 25 1969

1-10S-17W

15-103-20233

DRILLER'S LOG

COMPANY
CONTRACTOR
FARM
LOCATION

COMMENCED
COMPLETED

TILCO, ET AL
LEBEN DRILLING, INC.
KLIM #5
SE NW NW SECTION 1-10S-17W
ROOKS COUNTY, KANSAS
8-14-69
8-21-69

0	55	Surface Clay, Sand, Post Rock
55	209	Shale, Sand, Blue Shale
209	750	Shale
750	920	Sand, Shale
920	1140	Red Bed
1140	1220	Red Bed
1220	1258	Anhydrite
1258	1580	Shale
1580	1780	Shale
1780	2095	Lime with Shale
2095	2255	Lime, Shale
2255	2410	Lime, Shale
2410	2535	Lime with Shale
2535	2720	Lime, Shale
2720	2830	Lime, Shale
2830	2955	Lime, Shale
2955	3032	Lime
3032	3130	Lime
3130	3216	Lime
3216	3295	Lime
3295	3370	Lime
3370	3425	Lime
3425	3497	Lime
3497	3530	Lime
3530	<u>3545</u>	<u>Lime TD</u>



8 5/8" 20# new casing set @ 209' cement with 150 sacks Common 2% cc.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Klim #5 Well, located SE NW NW of Section 1, Township 10S, Range 17 West, Rooks County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)

SS