

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-163-30335

Company. MURFIN DRILLING CO.
 Farm. R. O. Cromwell No. 1


SEC. 2 T. 10 R. 17W
 SE SE NW

Total Depth. 3536
 Comm. 10-13-55 Comp. 10-23-55
 Shot or Treated.
 Contractor. Murfin Drilling Co.
 Issued. 1-28-56

CASING:

8 5/8 @ 161' w/ 125 sx cmt.

County Rooks
 KANSAS



Elevation. 2044 DF

Production. Dry

Figures indicate Bottom of Formations.

sandy shale	15
post rock	45
shale	120
shale & shells	460
shale, sand & shells	550
shale & shells	875
sand & shale	1061
red bed & shale	1283
anhydrite	1318
shale & shells	1625
salt & shale	1770
shale, lime & shells	1935
lime & shale	3238
lime	3325
lime & shale	3473
cherty conglomerate	3510
conglomerate	3513
Arbuckle	3536
Total Depth	

TOPS:

Topeka	2934
Heebner	3154
Toronto	3171
Lansing-K. C.	3194
Base K. C.	3440
Conglomerate	3473
Arbuckle	3513

DST #1: 3194-3238, open 1 hr. moder.
 bl. rec. 90' SO&GCW, 120' SW, BHP 925#

DST #2: 3238-54, open 1 hr. wk. bl.
 rec. 55' SOCM, 30' OCM, BHP 315#

DST #3: 3266-3356, open 40 min. wk. bl.
 15 min. rec. 40' BHP 750#/20 min.