

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


15-163-00739

Company- DAVIS BROS.-TRANSIT CORP.
Farm- Lamb "A" No. 1

SEC. 2 T. 10 R. 17W
C SE SE

Total Depth. 3525'
Comm. 7-21-58 Comp. 8-1-58
Shot or Treated.
Contractor. Transit Corp.
Issued. 12-6-58

County Rocks
KANSAS



CASING:
8 5/8" 160' w/125 sx cem.
4 1/2" 3520' cem w/260 sx.

Elevation. 2037' RB

Production. 25 BOPD

Figures Indicate Bottom of Formations.

surface clay, sand	160
shale, shells	800
sand	940
shale, shells	1253
Anhydrite	1290
shale	1800
lime, shale	2040
lime, shale stks	2215
lime, shale	2330
shale w/lime stks	2400
shale	2625
shale, lime stks	2790
lime, shale	2837
shale	2926
lime	3146
lime, shale	3230
lime	3258
lime, shale	3313
lime	3484
lime, Simpson conglomerate	3498
Arbuckle	3525
Total Depth	

TOPS: ELECTRIC

Anhydrite	1253-90' (driller)
Topeka	2920
Heebner	3141
Toronto	3167
Lansing-Kansas City	3188
Kansas City Base	3428
Marmaton sand	3432
Simpson shale	3484
Arbuckle	3495

Ran Schlumberger log.

DST #1 3093 3146 Open 80 mins. Started plugging after 15 mins. Weak 40 min blow. Rec. 115' of mud, 20 min IBHP 1120#, 20" FBHP 1030#. IFP 50#. FFP 75#.

DST #2 3145-3230 Open 1 hr. Rec. 15' mud. 20" FBHP 710#. IFP 36#. FFP 44#.

DST #3 3225-3258 Fairly strong 2 hr. blow. Rec. 135' of muddy wtr. and watery mud, all slightly oil cut. 20" FBHP 1033#. IFP 120#. FFP 180#.

DST #4 3249-3430 Open 2 hrs. Rec. 360' of heavy oil & GCM and 90' of oil and GCM. 20" IBHP 1118#. 20" FBHP 1026#. IFP 180#. FFP 325#.