

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-163-00585


Company- ANSCHUTZ DRILLING COMPANY, INC.
 Farm- Loreg No. 1

SEC. 2 T. 10 R. 17W
 SW NW SW

Total Depth. 3502
 Comm. 5-26-52 Comp. 6-8-52
 Shot or Tested.
 Cased.
 Landed. 7-5-52

County Rooks

KANSAS



8 5/8" casing: 177' cem w/100 sx

Elevation. Est. 2034 DF

Production. dry

Figures indicate Bottom of Formations.

clay, sand	174
shale, shells	265
shale blue, shells	610
red bed, shale	670
sand	730
shale, shells	850
sand	950
shale, red bed	1125
red bed	1280
anhydrite	1315
shale, shells	1752
shale, lime	1830
lime	1918
lime, shale	2090
lime	2174
lime, shale	2534
lime brkn, shale	2550
shale	2615
shale, shells	2767
lime, shale	3019
lime	3134
lime, shale	3188
lime	3314
lime congl	3486
arbuckle	3502
Total Depth	

Tops:

Anhydrite	1280
Heebner	3144
Toronto	3164
Lansing	3187
Cherty Conglomerate	3457
Simpson Dolomite	3459
Simpson shale	3465
Arbuckle	3486