

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-163-00828

Company- MURFIN DRILLING CO.
Farm- Loreg No. 1

SEC. 2 T. 10 R. 17W
NW NW SE

Total Depth. 3537

Comm. 8-1-55

Comp. 8-12-55


Shot or Treated.

Contractor. Murfin Drilling Co.

Issued. 12-10-55

County Rocks

KANSAS



CASING:
8 5/8 @ 181' w/ 120 sx cmt.
5 1/2 @ 3532' w/ 100 sx cmt.

Elevation. 2063 DF

Production. 135 BOPD

Figures indicate Bottom of Formations.

shale & sand	30
shale	125
shale & shells	490
sandy shale	833
shale, sand & shells	935
sand	1045
red bed	1100
shale & sand	1290
anhydrite	1334
shale & shells	1645
salt & shale	1785
shale & shells	1800
shale, lime & shells	1970
lime & shale	3321
lime	3423
lime & shale	3531
Arbuckle lime	3537
Total Depth	

TOPS:

Anhydrite	1290
Topeka	2951
Heebner	3172
Toronto	3193
Lansing-KC	3214
Base K. C.	3458
Conglomerate	3493
Arbuckle	3531

DST #1: 3212-55, open 1 hr. SI 30
min. rec. 10' HO&GCM, 90' O&GC muddy
wtr. 30' SO&GC muddy wtr. 180' wtr.
BHP 1105#

DST #2: 3262-90, open 30 min. SI 15
min. strong blow thruout. rec. 1710'
gas, 30' HO&GCM, 240' glassy froggy
oil. BHP 1040#

DST #3: 3298-3321, open 1 hr. wk. bl.
3 min. rec. 10' mud w/ few specks oil,
BHP 0#.

DST #4: 3384-3427, open 1 hr. wk. bl.
4 min. rec. 30' mud, BHP 0#/15 min.