

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-163-30147

Company- DAVIS BROS.-Transit CORP.
Farm- Dice Unit No. 4

SEC. 6 T. 10 R. 17W
SE NE SW

Total Depth 3570
Comm. 11-28-65

Comp. 12-5-65


Shot or Treated.

Contractor. Transit Corp.

Issued. 3-12-66

County Rocks

KANSAS



Elevation. 2106.1 RB

Production. 20 BOPD, WTR.

CASING:

8 5/8" @ 151' w/120 sx.
4" @ 3569' w/275 sx.

Figures indicate Bottom of Formations.

clay, sand & gravel	125
blue shale	151
shale	583
shale w/sand	600
shale	895
sand	1110
shale & red bed	1401
anhydrite	1436
shale & shells	1950
lime & shale	2250
lime	2385
lime & shale	2550
lime	2740
shale & lime	3033
lime	3530
lime & chert	3570
Total Depth	

TOES: Scout

Anhydrite	1401
Topeka	3033
Heebner	3251
Toronto	3269
Lansing	3292
" A Zone	3292-3319
" B "	3326-40
" D "	3346-61
" F "	3368-78
" G "	3380-3416
" H "	3422-41
" I "	3447-59
" J "	3461-74
" K "	3485-3502
" L "	3506-15
Base Kansas City	3515
Conglomerate	3528