

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-163-00919

Company- DAVIS BROS.-TRANSIT CORPORATION
Farm- Ross "D" No. 1

SEC. 7 T. 10 R. 17W
SE NW SW

Total Depth. 3715'

Comm. 5-25-59

Comp. 6-6-59


Shot or Treated.

Contractor.

Issued. 2-27-60

County Rooks

KANSAS



Elevation. 2135' KB

Production. 35 BOPD

CASING:

8 5/8" 172' cem. w/125 sx.

Figures Indicate Bottom of Formations.

sand & shale	172
shale & sand streaks	410
shale & shells	920
sand	1150
shale & shells	1230
red bed & shale	1434
anhydrite	1472
red bed & shale	1600
shale & shells	1900
shale & pyrite streaks	2050 ✓
lime	2355
lime & shale streaks	2440
lime	2561
shale & lime	2695
lime	2780
lime & shale streaks	2875
shale w/lime	3095
lime	3620
conglomerate chert	3654
Simpson dolomite	3697
lime	3715
Total Depth	

TOPS:

Topeka	3076
Heebner	3295
Toronto	3317
Lansing	3338
Base of Kansas City	3572
Cherty Conglomerate	3585
Simpson	3653
Arbuckle	3686