

15-1163-30242

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **STERLING DRILLING**

SEC. 9 T. 10 R. 17W
 LOC. SW SE NE

FARM Jones

NO. 1

TOTAL DEPTH **3550'**

COMM. **3-10-67**

COMP. **3-18-67**


SHOT OR TREATED

CONTRACTOR **Sterling Drlg.**

ISSUED **4-22-67**

COUNTY **Rooks**

KANSAS



CASING

20	10	
15	8 5/8"	@ 155' w/125 SX
12	6	
13	5	

ELEVATION **2062' KB**

PRODUCTION **DRY/ARB**

FIGURES INDICATE BOTTOM OF FORMATIONS

LOG

CASING RECORD

0 - 155 Clay & Shale

Ran 3 joints 8-5/8" 20# new seamless casing, 143' pipe set at 155' K.B., Cemented with 125 sacks Sunset. Plug was down at 7:30 P.M.

155 - 1334 Shale

1334 - 1375 Anhydrite

1375 - 2020 Shale

2020 - 3043 Shale & Lime

3043 - 3550 Lime T.D.

Started plugging at 5:00 P.M. Filled hole with heavy mud to 500', 20 sacks regular cement through drill pipe, heavy mud to 150' with HOWCO plug and 20 sacks regular cement through drill pipe, heavy mud to 35', 8 sacks regular cement to surface, Finished plugging at 11:15 P.M. March 17, 1967. Plugger: Leo Massey, Hays, Kansas.

TOPS: SCOUT

Heehner	3196
Toronto	3212
ansing	3234
Pase Kansas City	3474
Arbuckle	3538