

8/19/81
KCC

CONFIDENTIAL

KANSAS

**WELL COMPLETION REPORT AND
DRILLER'S LOG**


State Geological Survey
WICHITA BRANCH

S. 9 T. 10S R. 17 **W**

Loc. SE SE SW

County Rooks

640 Acres
N



Elev.: Gr. 2038'

DF 2040' KB 2043'

API No. 15 — 163 — 21,389
County Number

Operator Horizon Petroleum Corporation			
Address Riverfront Place, 833 North Waco, Wichita, Kansas 67203			
Well No. #1		Lease Name Plainville East	
Footage Location feet from (N) <u>330'</u> line feet from (E) <u>2310'</u> line			
Principal Contractor Circle M Drilling		Geologist Don Moore/ Wayne Merchant	
Spud Date 8-3-81	Date Completed 8-19-81	Total Depth 3600'	P.B.T.D.
Directional Deviation none		Oil and/or Gas Purchaser Koch	

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface Casing	12 1/4"	8 5/8"	20#	214'	Common	150	
Production Cas.	7 7/8"	4 1/2"	10.5#	3600'	Common	170	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		3516' - 3518'

TUBING RECORD		
Size	Setting depth	Pecker set at
2 3/8"	3600'	


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used Acidized with 250 gallons mud acid	Depth interval treated RELEASED Date: <u>AUG 1 1983</u> FROM CONFIDENTIAL
--	---

INITIAL PRODUCTION

Date of first production 9-24-81		Producing method (flowing, pumping, gas lift, etc.) Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil 160 bbls.	Gas None MCF	Water None bbls.	Gas-oil ratio N/A	CFPB
Disposition of gas (vented, used on lease or sold) N/A			Producing interval (s) 3516' - 3518'		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Horizon Petroleum Corporation		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Oil		
Well No. #1	Lease Name Plainville East			
S 9 T 10S R 17 E W				
WELL LOG <small>Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.</small>		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.		
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Topeka	2980'		Compensated Density Log	3604'
Heebner	3200'		Dual Laterolog	3595'
Lansing - Kansas City	3240'		Neutron Correlation Log	3603'
Conglomerate - Base of Kansas City	3512'			
Arbuckle	3564'			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				
Date Received	<div style="text-align: right; margin-bottom: 10px;">  _____ Signature </div> <div style="text-align: right; margin-bottom: 10px;"> Administrator _____ Title </div> <div style="text-align: right;"> 10-21-81 _____ Date </div>			

8207L