

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas


15-163-01847

Company- The BAY PETROLEUM CORPORATION
Farm- Hahn No. 2

SEC. 31 T. 10 R. 17W
SW NW SE

Total Depth. 3630 DF
Comm. 11-6-51 Comp. 1-11-52
Shot or Treated.
Contractor. Lindsley Drilling Co.
Issued. 5-24-52

County Rooks
KANSAS



CASING:

8 5/8" 151' cem w/100 sx
5 1/2" 3629' cem w/250 sx

2017 (2nd)
Elevation. 2075 DF

Production. potential 27.60 BO /
80% water

Figures Indicate Bottom of Formations.

clay, rock	40
clay shells	151
shale, clay, shells	797
shale, clay	1020
red bed sand	1060
shale, red bed breaks	1290
anhydrite	1380
shale, chalk lime	1515
lime, shale	3265
lime	3369
lime, shale	3430
lime	3468
lime, shale	3500
lime	3522
lime, shale	3611
lime	3630
Total Depth DF	

Tops:

Heebner	3248
Toronto	3268
Lansing	3290
Conglomerate	3543
Arbuckle	3628

DST: 3349-66 Open 1 hr,
30' mud, 900#
DST: 3444-79 Open 1 hr,
50' SOCM, 290#.
DST: 3476-3519 Open 1 hr,
Rec. 15' oil spkd mud 3'
HOCM, free oil in tool
540#.

DP- Swab 5 BOPH / SW. 400'
OB -2030' FU/12 hrs.