

Plotted Texas 15-63-01850
Plotted
In.


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

BAY PETROLEUM CORP.
Kompo No. 1-A.

SEC. 31 T. 10 R. 17W.
SW SE SW
330' fr S.L. 330' fr WL of
E $\frac{1}{2}$ SW $\frac{1}{4}$

Total Depth. 3589
Comm. 9-17-39 Comp. 10-3-39
Shot or Treated. 500 and 1000 gal acid.
Contractor. Manning and Martin.
Issued. 10-28-39

County. Rocks.



CASING.

103/4" 1312'
7" 3583'

Elevation.

Production. Pot. 45 BPH.

Figures Indicate Bottom of Formations. after acid.

shale blue	230
shale and sholls	995
rod beds and shale	1165
shale and sholls	1275
rod bed and anhydrito	1315
anhydrito	1355
shale	1481
rod bed and sholls	1675
shale	1720
salt	1839
shale and sholls	2100
limo	2355
broken limo	2467
limo and shale	2704
shale	2747
shale and limo	2880
shale	2980
limo	3510
conglomerate shale	3576
Simpson shale	3584
Arbucklo dolomito	3588
Simpson sand	3586
Arbucklo dolomito	3589

Total Depth.

Top Arbucklo 3583

2500' OIH 30 hours 2900' after acid. 3584-3589