

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-163-01853

Company- BAY PETROLEUM CORPORATION
Farm- Kempe "A" No. 4

SEC. 31 T. 10 R. 17W
NW NE SW

Total Depth. 3642 RB
Comm. 7-8-51 Comp. 7-22-51
Shot or Treated.
Contractor. Pickrell Drlg Co.
Issued. 10-6-51

County Rooks
KANSAS



CASING:

8 5/8" 143' cem w/75 sx
5 1/2" 3635' cem w/250 sx

Elevation. 2077

Production. 124 bbls

Figures Indicate Bottom of Formations.

MEASUREMENTS ARE FROM TOP ROTARY BUSHINGS.

cellar	5
surface hole	143
shale, sand	1060
shale, lime	1350
anhydrite	1390
shale	1710
shale, lime	1910
shale	2050
shale, lime	2270
lime	2380
lime, shale	2570
lime	2695
shale	2910
shale, lime	3 010
lime	3118
lime, shale	3175
lime	3642 RTD
Total Depth	

Tops:

Topeka	3032
Heebner	3255
Toronto	3276
Lansing	3297
Conglomerate	3551
Arbuckle	3633

S.L.M. 3300 OK.

DST: 3213-36 Open 30 min.
Rec. 690' salt water

DST: 3330-43 Open 40 min.
rec. 1285' salt water BHP 530#.

DST: 3467-3522 Op. 45 min. Rec.
30' mud.

DST: 3634-37 Open 30 min. Good
blow. Rec. 225' oil & muddy oil
& 60' heavily oil cut mud, 790# BHP