

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-163-01854

Company- THE BAY PETRO. CORP.
Farm- Kempe "A" No. 5

SEC. 31 T. 10 R. 17W
SE NE SW

Total Depth. 3639
Comm. 8-24-51 Comp. 9-4-51
Shot or Treated.
Contractor. Pickrell Drlg.
Issued. 11-10-51

County Rooks
KANSAS



CASING:

8 5/8" 161' cem w/100 sxs.
5 1/2" 3639' cem w/250 sxs.

Elevation. 2082

Production. 91 BO &
73 % wtr.

Figures Indicate Bottom of Formations.

cellar	5
surface hole	161
shale, shells	608
sand	710
sandy shale	878
sand	1008
partise iron	1120 ✓
red bed, shale, iron	1325 ✓
shale	1360
anhydrite	1395
shale, shells	1740
shale	2080
shale, shells	2320
lime	2410
lime, shale	3090
lime	3310
lime, shale	3358
lime	3635
arbuckle	3639 RTD
Total depth	

Tops:

Heebner	3254
Toronto	3273
Lansing	3295
Conglomerate	3551
Arbuckle	3633

DST 3457-3503 open 1 hr. 10"
rec. 130' oil and gas cut mud
BHP 960#
DP 2100' fluid 97% wtr.
sqz 9 BO & 19 BWP, 500 acid
70 BFP 75 % wtr.

SIM at 2000, 2500, & 3000 OK