

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

15-102-025-11

Plotted


REPUBLIC NAT. GAS CO.
Riddler No. 2-A.

Plotted Texas CO.

SEC. 31 T. 10 R. 17W
CW $\frac{1}{2}$ SW SW

Total Depth. 3606' = 3604 DF
Comm. 10-28-39 Comp. 12-3-39
Shot or Treated. No.
Contractor. Iron Drlg. Co.
Issued. 12-23-39 Rotary

County. Rooks



CASING:

13 " 107'
5 $\frac{1}{2}$ " 3601'

Elevation.

Production. Pot. 15,232 B.

Figures Indicate Bottom of Formations. Depth, No wtr

shale & shells	530	Rotary Cored:
sand	590	Cored 3597-3604 a total of
sdv shale	685	7', recovery 2'
shale & shells	835	6" sdv cherty pyritic green
sand	970	shale
shale & shells	1040	4" White chert, w/parts of
red beds	1163	lime, sdv shale, oil strkd
red beds & shale	1208	14" Arg., dense dolomite,
shale, lime, shells	1260	strkd saturation, few
red beds & shale	1312	cracks, poor porosity
anhydrite	1365	No cable tool coring
shale & lime	1378	
red beds & shale	1420	
shale & shells	1545	
lime	1550	
shale sticky	1560	
shale & shells	1680	
salt	1782	
shale	1860	
lime	1877	
shale & lime	1986	
shale	2004	
lime	2093	
shale & lime	2185	
lime	2450	
shale & shells	2468	
lime	2475	
brkn lime & shale	2567	
shale & lime	2628	
lime	2690	
shale & lime	2775	
shale	2855	
lime	2913	
shale & lime	3088	
brkn lime	3148	
lime	3185	
shale & lime	3279	
lime	3309	
shale	3311	
brkn lime & shale	3350	
lime	3441	
shale & lime	3465	
lime sft	3477	
shale & lime	3531	
brkn lime & chert	3562	
shale & lime	3565	
lime & chert	3573	
lime	3575	
shale red & green	3599	
cored	3606	
3606 equals 3604		
lime	3604	

Total Depth

Tops: Lansing 3270

Cong. cherty DF 3524

Simpson dolo. DF 3570

Arbuckle DF 3602