

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-163-00726

Company- THE BAY PETROLEUM CORP.
Farm- Ridler "K" No. 1

SEC. 32 T. 10 R. 17W
NW NW SW

Total Depth. 3658
Comm. 1-8-54 Comp. 1-25-54
Shot or Treated.
Contractor. Lewis Drlg. Co.
Issued. 3-27-54

County Rocks KANSAS



Elevation. 2034 DF

Production. 99 BO & 1% wtr.

Figures indicate Bottom of Formations.

shale	192
shale & shells	825
sand	915
shale & shells	1310
anhydrite	1335
shale & lime	2475
shale	2560
shale & lime	3200
shale	3220
lime & shale	3250
lime	3289
lime & shale	3320
lime	3490
lime & shale	3560
conglomerate	3590
lime	3594
conglomerate	3612
arbuckle lime	3658
Total Depth	

Tops:	
Heebner	3221
Toronto	3237
Lansing-Kansas City	3259
Conglomerate	3511
Simpson ¹ / ₂ olo.	3581
Arbuckle	3606

DST: 3325-48' open 1 hr.
rec. 170' gas 130' HOCM
BHP 1200#.

DST: 3410-40' open 1 hr.
rec. mud, few specks oil
600# BHP

DST: 3440-75' open 1 hr.
rec. 10' mud "0" BHP

DST: 3582-89' open 1 hr.
rec. 26' mud 1180# BHP.

DST: 3606-10' open 1 hr.
rec. 65' mud. 1040# BHP.

DST: 3609-15' open 1 hr.
rec. 35' thin drlg. mud.
BHP 1020#.

Gamma Ray-Perf. 64 3426-28
NS 1000 acid, $\frac{1}{2}$ BFPH. 50% wtr.
LWP 2410 perf. 12% 3396-3400-106 WPH
perf. 12% 3360-64 -426 WPH
LWP 3350 perf. 24% 3340-46- 26 wtr
4 GO/15 mins.
1000 acid, swab 7 BOPH no wtr.