

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-163-71922

Company- TENNESSEE GAS TRANSMISSION COMPANY
Farm- Ridler "K" No. 2

SEC. 32 T. 10 R. 17W
SW SW SW

Total Depth. 3593'
Comm. 2-27-57 Comp. 3-13-57
Shot or Treated.
Contractor. Shelley-Miller Drilling Company
Issued. 4-27-57

County Rocks KANSAS



Elevation. 1941' KB

CASING:

8 5/8" @1211' w/600 sx cem.

Production. Dry

Figures indicate Bottom of Formations.

Measurements from top of Rotary Bushing to Bottom of Formation

Ground Level	
to Kelly	4
Post Rock	35
sand	50
shale & shells	680
sand	850
red bed	885
red bed & Pyrite	1190 ✓
Red Bed	1206
Anhydrite	1235
Red Bed	1250
shale & shells	1760
lime & shale	2755
lime	3532
Dolomite	3593 RTD
Total Depth	

TOPS	
Anhydrite (Scout)	1202
Heebner	3131
Toronto	3151
Lansing/Kansas City	3173
Conglomerate	3436
Simpson	3491
Arbuckle	3512