

May, 1936.

Lario #1 Fisher,
NE corner, 22-10S-18W,
Elevation 2148' *PF*

Pennsylvanian conglomerate No conglomerate proper.

Ordovician Top 3670'

Sub-sea, minus 1522'

Viola 3670-3733'

3670-3733 Chert, residuum in place. Somewhat porous at top; with a few pieces of chert oilstained and with considerable asphaltic material in holes in chert. Some lime is present below 3710' but it is only a minor quantity and may not be bedded.

Decorah 3733-3775

3733-3743 Clay, dark red.

3743-3749 Dolomite, white to pink.

3749-3775 Shale, green, maroon, and chocolate, sandy, phosphatic.

3733
2148
1585

Arbuckle Top 3775' Penetration 6'

Sub-sea, minus 1627'

3775-3781 Probably Miller-Purcell. Sequence not long enough for positive check but criteria are not out of line.