

State Kansas County Rooks

Sec. 18 Twp. 10 Rng. 19W Elev. 2229

Company Birmingham & Bartlett

Well No. 3 Name Margotta "A"

Location SW SW NW

Feet from lines: N. S. E. W.

Spud 9-19-19 Completed 12-7-19

T. D. 3781 Casing 5" 3767

PB 3750

Comp. Perf. 115 3596-3606

Pay 3596-3606 in Laus.

I. P. 761 TOPD

Choke T. P. C. P.

G. O. R. Grvty.

DATE	REMARKS
12-7-19	Anhy. 1640, Heeb. 3424, Tor. 3441, Laus. 3462, Gr. 3701, Simp. 3753, Arb. 3765, DST 3508-30, open 30' min., rec. 110' salt mbr.,

COMPLETION
709

DATE	REMARKS
	DST 3513-48, open 15 min., rec. 420' oil, no wtr., BHP 1220#.
	DST 3551-56, open 30 min., rec. 27' OCM.
	DST 3582-3605, open 10 min., rec 450' oil, no wtr., BHP 1250#.
	DST 3605-45, open 30 min., rec. 90' O & OCM, BHP 800#.
	RTD 3768.
	DP TD FU 900' oil & wtr/1 hr. 45 min., Swb/42 BF, mostly oil, Sqz. shoe.
	5 $\frac{1}{2}$ 1685, Sqz.
	DP DD 3769, Swb/7 BO $\frac{1}{2}$ 7 BPPH
	DD 3771, Swb/7 BO $\frac{1}{2}$ 89 BF.
	DD 3773, GSO, PB 3772, OO TD Swb/40 BF/7 hr., 70% wtr.
	DD 3781, Swb/10 BPPH, mostly wtr/3 hrs.
	PB 3750, 47 $\frac{1}{2}$ 3596-3606, B/1/4 OOML, 1000 A, Swb/50
	BOPH, 2400' off bta.
	Phy. pot. 761 BOPD, no wtr.
	COMPLETE
	668529