

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-163-00508

Company- D. & M. DRILLING CO.
Farm-Minnie E. Allisor No. 1

SEC. 4 T. 10 R.18W
SE SW SW

Total Depth. 3765

Comm. 5-13-53

Shot or Treated.


Contractor.

Issued. 6-27-53

Comp. 5-24-53

County Rooks

KANSAS



CASING:

8 5/8 189' w/ 150 sx cement

Elevation. 2187 KB

Production. Dry

Figures Indicate Bottom of Formations.

shale & sand	186
shale	560
Dakota sand	1030
iron	1038
sand	1265
shale & red bed	1568
anhydrite	1616
shale	2140
lime & shale	2290
lime	2360
shale	2510
lime & shale	2635
shale	2810
lime & shale	2905
shale & lime streaks	3095
lime	3536
lime & shale streaks	3576
lime	3638
conglomerate	3663
lime, chert streaks & shale	3720
lime & shale	3759
lime	3765
Total Depth	

TOPS:

Topeka	3151
Heebner	3366
Toronto	3384
Lansing	3408
Conglomerate	3638
Simpson	3726
Arbuckle	3759