


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- DAVIS BROS. & TRANSIT CORP.
Farm- Gilbert No. 1

SEC. 5 T. 10 R. 18W
SW NW SW

Total Depth. 3827'
Comm. 4-28-58 Comp. 5-11-58
Shot or Treated.
Contractor. Transit Corp.
Issued. 7-26-58

County Rooks
KANSAS



Elevation. 2199' KB

Production. Dry

CASING:

8 5/8" 180' cem w/135 sx.

Figures Indicate Bottom of Formations.

surface clay	50
shale & shells	100
sand	160
shale	390
shale & shells	850
sand	1044
shale & shells	1605
Anhydrite	1640
shale & shells	2080
shale & shells w/lime streaks	2185
lime & shale	2525
shale w/lime strks	2570
shale	2673
shale & lime	2997
lime & shale	3052
lime & shale strks	3109
shale w/lime strks	3175
lime & shale	3446
lime & shale strks	3535
lime & shale	3581
lime & shale strks	3630
lime & shale	3685
cherty Conglomerate	3771
Simpson	3780
Simpson Dolomite	3806
Simpson, Dolomite & Arbuckle	3827 RTD
Total Depth	

TOPS:

Anhydrite (scout)	1605
Topeka	3171
Heebner	3389
Toronto	3410
Douglas	3422
Lansing	3432
Base Kansas City	3660
Conglomerate	3683
Shale Conglomerate	3760
Simpson	3766
Arbuckle	3806