

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas


Computer Inventoried
15-103-04048

Company- THE ATLANTIC REFINING COMPANY
Farm- Elizabeth C. Ordway No. 1

SEC. 8 T. 10 R. 18W
NE NE SE

Total Depth. 3743
Comm. 2-20-53 Comp. 4-3-53
Shot or Treated.
Contractor. Spears Drlg. Co.,
Issued. 5-23-53

County Rooks
KANSAS



Elevation. 2189 DF

Production. 533 BOPD & NW

CASING:

10 3/4" 1591' RKB cem. w/1300 sx
7" 3720' RKB cem. w/500 sx
5 1/2" 3738' cem. w/30 sx

Figures Indicate Bottom of Formations.

gravel	40	Acidized open hole with
gravel & sand	110	500 gals. 15% hydrochloric
shale & sand	285	acid and 3 gals. Morflo.
shale, sand & chip	410	Re-acidized with 750 gals.
shale	507	15% hydrochloric acid &
shale & shells	680	3 gals. Morflo.
shale & sand	850	
sand	865	
shale & shell	1020	
shale, shells, iron	1030 ✓	
shale, sand, iron	1270 ✓	
sand, iron	1340 ✓	
sand, shale & iron	1350 ✓	
sand & iron	1410 ✓	
shale, sand & iron	1480 ✓	
shale & red bed,		
iron	1570 ✓	
iron & anhydrite	1592	
anhydrite, lime	1620	
anhydrite, & shale	1660	
shale	1865	
shale & lime	1900	
shale & lime strks	2115	
shale	2205	
shale & lime	2305	
lime	2355	
lime & shale	2854	
shale & lime, brkn	2890	
shale	3020	
lime & shale	3080	
shale & lime strks	3115	
shale	3165	
lime & shale	3335	
lime & shale, brkn	3360	
lime & shale	3485	
lime	3558	
lime & shale, brkn	3570	
lime	3584	
lime & shale	3620	
lime	3633	
lime & shale	3715	
lime	3722	
shale	3735	
shale, dolomite	3737	
dolomite	3743	
Total Depth		

Scout Tops:

Topeka	3146
Heebner	3363
Toronto	3379
Lansing	3403
Congl.	3642
Simpson Dolomite	3698
Arbuckle	3737