

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

15-163-10935


Company- MID-STATES OIL CORPORATION
Farm- Wise No. 2

SEC. 8 T. 10 R. 18W
NW SE NE

Total Depth. 3743
Comm. 4-9-53 Comp. 4-23-53
Shot or Treated.
Contractor. M. B. Armer
Issued. 6-20-53

County Rooks

KANSAS



CASING:

8 5/8 set at 1587' w/ 800 sx cement
5 1/2 set at 3740.5' w/ 200 sx cement

Elevation. 2192 KB

Production Phys. Pot. 397 BO

Figures Indicate Bottom of Formations.

surface sand & gravel	99
sand & shale	465
sandy shale & lime	845
shale & sand	1025
sand, chert & iron	1050 ✓
sand	1160
sand, red bed & iron	1577 ✓
anhydrite	1587
anhydrite & iron	1660 ✓
red bed, shale & sand	1895
shale, shells & salt	2120
shale & lime	2190
shale & shells	2290
shale & lime	2864
shale & broken lime	3150
shale & lime	3275
lime	3430
shale & lime	3512
cherty lime & broken shale	3565
lime	3604
shale & lime, some chert	3647
chert & lime	3689
shale & lime	3743
Total Depth	

TOPS: (RB Meas.)

Anhydrite	1577
Topeka	3149
Heebner	3364
Toronto	3381
Lansing KC	3406
Conglomerate	3639
Top Simpson	3700
Arbuckle	3742

Phy. Pot. 397 bopd from Arb.

R.T.D. 3742