

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-103-01856

Company- A. W. HOLIDAY OIL CO.
Farm- Williams No. 1

SEC. 9 T. 10 R. 18W
SW NW NW

Total Depth. 3780'
Comm. 11-10-55 Comp. 11-22-55
Shot or Treated.
Contractor.
Issued. 3-31-56

County Rooks KANSAS



Elevation. 2192' KB

Production. 46 BO

CASING:

8 5/8" 212' cem w/150 sx
5 1/2" 3779' cem w/175 sx

Figures indicate Bottom of Formations.

rock - clay	40
shale - sand	150
shale	212
shale - sand	1025
shale - shells	1190
sand	1280
red rock shale	1571
anhydrite	1600
shale - lime	3181
lime	3653
chert - lime	3711
chert - lime - shale	3738
lime	3780
Total Depth	

Tops:

Topeka Limestone	3152
Hebner Shale	3368
Toronto Limestone	3386
Lansing-Kansas City	3410
Shaley Conglomerate	3635
Cherty Conglomerate	3646
Arbuckle Dolomite	3747

DRILL STEM TESTS:

- #1 3326-53', open 1 hr., closed 20 min. weak steady blow. Rec. 275' slightly oil cut watery mud. BHP 960# FFP 240#.
- #2 3376-3403', open 1 hr., closed 20 min. Weak blow for 22 min. Rec. 30' SOCM/ BHP 880#. FFP 0#.
- #3 3399-3427', open 1 hr., closed 20 min. Weak intermittent blow throughout. Rec. 300' mud. BHP 290#
- #4 3447-77', open 1 hr., closed 20 min. Weak steady blow. Rec. 30' mud. BHP 480#.
- #5 3477-3508', open 1 hr., closed 20 min. Weak steady blow. Rec. 240' fluid. (180' slightly oily and gas cut mud and 60' very heavily oiled and gas cut mud.) BHP 460# FFP 130#.
- #6 3546-84', open 1 1/2 hr., closed 20 min. Fair diminishing blow. Rec. 287' very heavily oiled and gas cut mud. BHP 1080#. FFP 140#.
- #7 3733-51', open 1 1/2 hrs., closed 20 min. Good blow throughout. Rec. 1305' of oil and gas cut sulphur water. BHP 920# IFP 120# FFP 590#.