

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-163-00758

Company- DAVIS BROS.
Farm- Jones No. 1

SEC. 10 T. 10 R. 18W
NE NE NE

Total Depth. 3795'
Comm. 4-29-58 Comp. 5-13-58
Shot or Treated.
Contractor. Leben Drilling, Inc.
Issued. 6-28-58

County Rooks
KANSAS



CASING:
8 5/8" 192' cem w/150 sx.

Elevation. 2151' KB

Production. Dry

Figures Indicate Bottom of Formations.

surface sand	30
sand & shale	90
blue shale	192
shale	610
shale & sand	715
shale	1010
sand	1215
redbed & shale	1492
Anhydrite	1532
shale & shells	1805
lime & shale	2630
shale	2650
shale & lime	3120
lime	3764
dolomite	3795 RTD
Total Depth	

TOPS:	
Anhydrite	1492
Topeka	3127
Heebner	3343
Toronto	3365
Lansing	3387
Base Kansas City	3618
Marmaton Lime	3624
Marmaton Cherty Limestone	3636
Marmaton Chert	3641
Conglomerate	3647
Reworked Simpson	3700
Simpson	3724
Simpson Dolomite	3735
Arbuckle	3755

Ran Electric log: Radiation-Guard Log.

DST #1 3541-3603, op 2 hrs, weak blow
rec. 15' SOCM, 30' mud w/a few specks
of oil. 20" ICIP 20#(false). 20" FCIP 160#
(maximum) FP 0#.