

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


15-163-03410

Company- DAVIS BROS. -TRANSIT CORP.  
Farm- Ordway "C" No. 3

SEC. 16 T. 10 R. 18W  
NW SW SW

Total Depth. 3711'  
Comm. 8-2-58 Comp. 8-16-58  
Shot or Treated.  
Contractor. Transit Corp.  
Issued. 12-20-58

County Rocks  
KANSAS



CASING:  
8 5/8" 173' cem w/125 sx.  
4 1/2" 3706' cem w/960 sx.

Elevation. 2145' KB

Production. 96 BOPD

Figures indicate Bottom of Formations.

clay & sand	173	#5 3552-3605, op 1 hr., rec. 30' mud, slightly oil specked. 20" IBHP 0#, FBHP 100#. FP 0#.
shale	625	
shale & shells	689	
sand	911	#6 3598-3686, op 2 hrs., rec. 830' of very heavy oil cut mud. 20" IBHP 830#, FBHP 610#, FP 60#-410#.
shale & shells	1000	
sand	1220	
shale & shells	1527	
Anhydrite	1555	
shale & red bed	1810	
shale	2025	
shale w/lime streaks	2140	
shale & lime	2420	
lime & shale	2532	
shale & lime strks	2717	
lime & shale	2785	
shale strks & lime	2827	
shale	2970	
lime & shale	3085	
shale & lime	3130	
lime & shale	3300	
lime	3327	
lime & shale	3376	
lime	3496	
shale	3520	
lime	3552	
shale strks	3558	
lime	3673	
chert	3686	
lime & shale	3711	
Total Depth		

TOPS:

Anhydrite	1522
Topeka	3114
Heebner	3330
Toronto	3347
Lansing	3371
Base of Kansas City	3601
Conglomerate	3615
Simpson Sand	3676
Simpson Dolomite	3684
Arbuckle	3704

Ran Schlumberger Laterolog Survey.

DRILL STEM TESTS:

#1 3272-3300, op 2 hrs., rec. 120' muddy salt water, few drops of oil. 20" IBHP 1150#, FBHP 1090#, FP 20#-60#.

#2 3334-3440, op 2 hrs., rec. 540' of slightly oil & gas cut muddy water. 20" IBHP 1000#, FBHP 770#, FP 40#-300#.

#3 3451-99, op 2 hrs., rec. 245' muddy salt water. 20" IBHP 650#, FBHP 570#, FP 20#-140#.

#4 3485-3558, op 2 hrs., rec. 180' SOGCM, 30' watery mud. 20" IBHP 120#, 25" FBHP 750# FP 40#-100#.