

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-103-00999

Company- DAVIS BROTHERS & TRANSIT CORPORATION
Farm- Ordway No. 1

SEC. 17 T. 10 R. 18W
SE SE NE

Total Depth. 3729'
Comm. 9-17-57 Comp. 10-1-57
Shot or Treated.
Contractor. Transit Corporation
Issued. 12-28-57

County Rocks KANSAS



Elevation. 2177' K.B.

Production. 45 BOPD

CASING:

8 5/8" @ 219' cem. w/125 sx
5 1/2" @ 3729' cem. w/700 sx

Figures indicate Bottom of Formations.

Surface clay	110
shale -	160
sand	195
shale & shells	1565
anhydrite	1600
shale-shells	2020
shale	2050
shale & lime	2645
lime & shale	2965
shale & lime	3230
lime & shale	3340
shale & lime	3390
lime & shale	3423
lime	3426
lime & shale	3460
lime	3600
lime & shale	3665
shale - chert lime	3700
lime	3721
simpson - shale	3725
lime	3729 RTD
Total Depth	

TOPS: (Electric Log)

Anhydrite (driller's top)	1565
Topeka	3147
Heebner	3361
Toronto	3375
Lansing	3401
Base of Kansas City	3632
Conglomerate	3650
Simpson Shale	3684
Definite Simpson Shale	3703
Simpson Dolomite	3728

D.S.T. #1. 3364-3390 Open 2 hrs.
Rec. 235' gas, 120' HOCM, 65' VHO CM.
FP 30#-90#. 15" ISIP 1198#. 20"
FSIP 1025#.

D.S.T. #2. 3389-3426 Open 2 hrs. Rec.
413' gas, 27' SO&GCM. 120' VHO&GCM.
60' GCO. FP 42#-120#. 15" ISIP 1167#
20" FSIP 1062#.

D.S.T. #3. 3423-3450 Open 2 hrs.
Rec. 150' SOCM and OCM. FP 23#-90#.
15" ISIP 424#. 20" FSIP 337#.

D.S.T. #4. 3446-3475 Open 1 hr. Rec.
1988' gas, 1312' oil. FP 54#-485#.
15" IBHP 653#. 20" FBHP 629#.

D.S.T. #5. 3710-3721 Open 1 hr. Rec.
10' mud. All pressures 0#.