

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15-103-01806

Company- DAVIS BROTHERS
Farm- Ordway "C" No. 2

SEC. 17 T. 10 R. 18W
NE NE SE

Total Depth. 3733'
Comm. 5-28-58 Comp. 6-3-58
Shot or Treated.
Contractor. Transit Corp.
Issued. 9-20-58

County Rooks
KANSAS



CASING:
8 5/8" 180' cem w/130 sx.
4 1/2" 3732' cem w/1000 sx.

Elevation. 2179' KB

Production. 105 BOPD

Figures Indicate Bottom of Formations.

clay, sand & shale	131
shale & shells	790
sand streaks	980
shale & shells	1040
sand	1230
shale	1300
shale & shells	1565
Anhydrite	1600
shale & shells	2070
shale & lime	2400
lime & shale	2520
shale & lime	2700
lime & shale	3115
shale & lime	3182
lime & shale	3260
lime	3644
cherty Conglomerate	3696
Conglomerate	3701
sand	3731
lime	3733 RTD
Total Depth	

TOPS:
Topeka 3138
Heebner 3353
Toronto 3368
Lansing 3394
Base Kansas City 3626
Conglomerate 3637
Simpson 3701
Simpson Dolomite 3712
Arbuckle 3731

DST #1 3295-3330, op 1 hr, rec. 240'
slightly oil cut muddy water, 20" IBHP
1160#, IFP 50#, FFP 150#, 20" FBHP 1125#.

DST #2 3352-3415, op 1 hr, strong blow,
rec. 30' SOGCM, 60' MOGCM, 60' HOGCM, 180'
VHOGCM, 60' MCO, 60' VHOGCM. 20" ICIP
1185#, 20" FCIP 1165#, FP 30# -160#.