

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-163-71983

Company- DAVIS BROTHERS
Farm- Ordway "C" No. 6

SEC. 17 T. 10 R. 18W
C NE SE SE

Total Depth. 3712'
Comm. 9-24-62 Comp. 10-5-62
Shot or Treated.
Contractor. Transit Corp.
Issued. 12-22-62

County Rocks
KANSAS



Elevation. 2141' DF

CASING:
8 5/8" 179' cem w/125 sx.

Production. DRY

Figures Indicate Bottom of Formations.

top soil	35
sand	40
shale	155
blue shale	181
shale	450
shale & shells	810
sand	850
shale w/pyrite streaks	1020
sand	1090
shale	1524
anhydrite	1560
red bed & shale	1960
shale	2050
shale & lime	2130
lime w/shale	2360
lime	2440
lime & shale	2575
shale w/lime	2665
shale & lime	2745
shale w/lime	2855
shale	3117
lime	3604
lime & chert	3640
conglomerate chert	3682
lime	3712 RTD
Total Depth	
TOPS: SAMPLE	
Anhydrite	1524
Topeka	3113
Heebner	3326
Toronto	3342
Lansing	3367
A Zone	3367 - 3391
B Zone	3400 - 3415
D Zone	3422 - 3433
E & F Zones	3436 - 3452
G Zone	3452 - 3482
G Zone Prime	3485 - 3489
H Zone	3499 - 3516
I & J Zones	3520 - 3549
K Zone	3551 - 3571
L Zone	3575 - 3582
M Zone	3586 - 3595
Base Kansas City	3595
Conglomerate	3612
Simpson Shale	3669
Simpson Sand	3671 - 3673
Simpson Dolomite	3676 - 3681
Simpson	3686 - 3692
Arbuckle	3706